No.	Items of work	Unit	Rate	Quantity
5	Old stone work resetting	C.yds.	0 12 0	510
6	New stone work with jelly packing ..	C.yds.	1 8 0	2,004
7	Do with available stone from blasting	C.yds.	0 12 0	121
8	Gravel backing behind new stone revetment at breach only	C.yds.	0 6 0	468
9	Providing and fixing chiselling figures and painting Register No. stone	Each	5 0 0	1
10	Do Bench Mark stones ..	Each	3 0 0	2
11	Do Gauge Stones	Each	12 0 0	1
12	Do Grades with Index stones ..	Each	2 8 0	18
	BREACH FROM C. S. 16 TO C. S. 19.			
1	Bailing water in breach	Lumpsum	..	50 rupees.
2	Clearing silt in breach	C.yds.	0 2 6	848
3	Earthwork excavation	C.yds.	0 3 0	200
4	Benching Rock	S.ft.	0 8 0	270
5	Core wall of brick in surki mortar	C.ft.	0 4 0	1,080
6	Earthwork mixtures of gravel and clay including watering and tamping	C.yds.	0 5 0	4,674
	REPAIRING WASTE WEIR OF LEFT EXISTING 70 FEET LONG AND RAISING THE SAME OT R. L. 52.00.			
1	Brick in surki mortar	C.ft.	0 5 0	394
2	Burnt stone slabs 6" thick	S.ft.	0 7 0	121
3	Plastering with surki mortar	Sqrs.	3 8 0	5.00
	EXTENSION OF THE EXISTING WEIR BY 220 FEET TO R. L. 52.00.			
1	Earthwork excavation	C.yds.	0 3 0	286
2	Blasting rock by Gun powder to open top gabs in obstruction in front of the apron for free flow of the weir discharge	C.yds.	1 8 0	239
3	Burnt brick in surki mortar	C.ft.	0 5 0	1,749
4	Burnt stone slabs 6" thick	S.ft.	0 7 0	286
5	Plastering with surki mortar	Sqrs.	3 8 0	9.50
6	Joggles of stone plugs	No.	0 8 0	36
7	Jelly wedging old apron	S.yds.	0 8 0	168
8	New stone apron with available blasted stones .	C.yds.	0 8 0	118

N. G. KRISHNA IYENGAR,
Executive Engineer.

CHITALDRUG DIVISION.

Notification dated 4th August 1936.

1. Sealed tenders will be received at the office of the Executive Engineer, Chitaldrug Division, Chitaldrug, up to 2 P.M., on 28th August 1936, for constructing Police Lines at Davangere.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Chitaldrug Division, Chitaldrug, on payment of Rupee one for each form should be addressed to the Executive Engineer, Chitaldrug Division, Chitaldrug, and should be superscribed as "Tender for constructing Police Lines at Davangere." The name of the tenderer should also be superscribed on the sealed cover.

3. Each tender must be accompanied by a deposit of Rs. 500, (Five hundred only) in cash or Government Promissory Notes or Mysore Government Bonds at face value or market value, whichever is less, as earnest money. The earnest money of the successful tenderer will be retained as security deposit for due fulfilment of the contract. (Cash amount will not carry any interest).

4. The tenders will be opened in the presence of such tenderers who wish to be present on 3rd Thursday of September 1936. The final acceptance of the tender will rest with the Superintending Engineer, Shimoga Circle who does not bind himself to accept the lowest or any tender, or to assign any reasons whatever, for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office, in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute the Agreement in the departmental schedule contract form for the due fulfilment of the contract.

6. Failure to comply with the Condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. Copies of contract documents, estimates and drawings, may be seen at any time at the office of the Executive Engineer, Chitaldrug Division, Chitaldrug, on all working days between 11 A.M. and 5 P.M.

8. Specific rate should be given for each item in the schedule and the rates should be in rupees, annas and in multiples of three pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

9. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates tendered should include all such lumpsum items.

10. No alterations which are made by the tenderers in the Contract documents in the nomenclature of the sanctioned sub-heads will be recognised and if corrections are made, the tenders will be liable to rejection.

11. There should be no corrections or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

12. No reference should be made to the Public Works Department current schedule of rates.

13. On the event of the tender being submitted by a Firm, it must be signed separately and severally by each member thereof, or in the event of absence of any partner, it must be signed on his behalf by a person holding power of attorney, authorising him to do so.

14. When once the rates tendered have been accepted they will not be revised under any circumstances. In regard to items of work not tendered, the rates to be proposed by the Executive Engineer, Chitaldrug Division, Chitaldrug, and approved by the Superintending Engineer, Shimoga Circle, shall be final and legally binding on the tenderer.

15. The quantities given in the schedule are only approximate and are liable to alterations, omissions, deductions, or additions, at the discretion of the Executive Engineer or his representative. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

16. The work should be completed and handed over to the Public Works Department within 30th June 1937, from the date from which the work is ordered to be commenced, failing which the Executive Engineer may, at his discretion, levy a penalty of Rs. 5 per day, which will be recovered from the Contractor's outstandings for the period by him till the work is completed and handed over.

17. In all matters of dispute of any kind, not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Superintending Engineer, Shimoga Circle shall be final and legally binding.

18. The earnest money of rejected tenders will be returned on submission of the receipts originally granted, along with an application, to the Executive Engineer, Chitaldrug Division, Chitaldrug.

19. No claims for damages, for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reason for such delays. Contractors should bear this in mind when tendering for work. Extension of time due to delays caused by the departmental officers will however be considered on the merits of each case.

20. The contract should not be sub-let.

21. All materials, tools and plant and machinery, old doors, windows, etc., that will be supplied by the Executive Engineer, in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer and the tenderers will pay the hire, etc., on machinery and tools and plant at the prescribed per cent per annum of the booked value of the tools and plant supplied from the date of taking over of tools and plant from the Stores to the date of return to the Stores. The dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The Contractors should arrange for the payment of Royalty and tools.

Note.—(A) The Contractor should at his own cost :—

(1) Provide rods, stakes, ropes and labours required in setting out the works.
(2) Provide all necessary scaffolding, entering labour and appliance for hoisting.
(3) Provide mortar mill and shed to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns, water-shoots, covering to masonry tile pieces to steps, sieves, parahs, or measures shoring and other requisite protection during the progress of the work.
(6) Supply all water required for work and workmen and shall provide latrines, drainages, etc.
(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.

(8) Provide arrangements for pumping and bailing from excavations and foundations, wherever and whenever necessary with his own pumping apparatus, including necessary leading drains, slump pits, pits, etc.

(9) Wash floors at completion and leave the whole of the work and premises in a clean and orderly condition, etc.

(10) Afford facilities to any other parties employed upon the work, so that their work may proceed during the progress of the contract and give such persons the use of ordinary scaffolding and ladders.

Note.—(B) It is the business of the Contractor to make his own arrangements for the quarries and supplies of materials.

23. The rates for wood work for all works quoted should be based on the rates of the departmental supply as noted below. Only Mysore Teak selected from the Mysore Depots must be used.

Prevailing Government rates at.....for

	Rs.	a.	p.	
(1) Selected 1st class logs	2	8	0	per C.ft.

24. If it is considered desirable, the work will be distributed to more than one contractor for the speedy completion of the work.

Abstract Estimate for Construction of New Police Lines at Davangere. (Two blocks.)

Sl. No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
1	Earthwork excavation	C.yd.	0 4 0	320	
2	Concrete in lime mortar	C.ft.	0 4 0	2,422	
3	Size stone in mud	C.ft.	0 4 0	6,664	
4	Burnt brick in mud	,,	0 4 0	7,412	
5	Do in chunam mortar	,,	0 4 6	1,038	
6	Burnt stone slabs dressed and fixed in mortar ..	S.ft.	0 6 0	736	
7	Teak wood doors battened with shutters including hingeses, bolts, etc., complete ..	S.ft.	1 8 0	612	
8	T. W. windows with single shutters with iron bars, hooks, hinges, etc., complete.. ..	,,	2 0 0	210	
9	Teak wood wrought and put up-including wood oiling	C.ft.	5 0 0	240	
10	Plastering with chunam mortar	Sqr.	3 8 0	174.68	
11	White washing two coats	,,	0 4 0	175.68	
12	Roofing with first class Mangalore tiles over teak reepers including railings, etc., complete	,,	35 0 0	50.22	
13	Flooring with 3″ lime concrete and cement plastering ¾″ thick	,,	15 0 0	28.08	
14	Cement pointing to basement	,,	4 0 0	9.88	
15	Brick in mortar coping	R.ft.	0 8 0	406	
16	Teakwood ornamental finials	Each	4 0 0	4	
17	Mortar bands over roof	R.ft.	0 4 0	316	
18	Chocolate painting	Sqr.	4 0 0	21.60	
19	Ridge tiles set in mortar and fixed	R.ft.	0 8 0	166	
20	Constructing drain set C for leading off water ..	..	Lumpsum		300
21	Unforeseen items of work	..	Lump sum		200

Abstract Estimate for Constructing an Havaldar's Quarter in Police Line, at Davangere.

Sl. No.	Items of work	Per	Rate	Quantity	Cost
			Rs. a. p.		Rs.
1	Earthwork excavation	C.yd.	0 4 0	55	
2	Jelly concrete	C.ft.	0 4 0	410	
3	Size stone in mud	,,	0 4 0	1,186	

Sl. No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
4	Burnt brick in mud	Cft.	0 4 0	1,113	
5	Burnt stone slabs 6″ thick dressed ..	S.ft.	0 6 0	161	
6	Burnt brick in mortar	C.ft.	0 4 6	342	
7	T. W. doors battened.....complete ..	S.ft.	1 8 0	126	
8	T. W. windows with iron bars	,,	2 0 0	48	
9	T. W. Ventilators	,,	1 8 0	24	
10	T. W. wrought and put up	C.ft.	5 0 0	46.14	
11	First class Mangalore tile roofing	Sqr.	35 0 0	9.52	
12	Ridge tiles set in mortar	R.ft.	0 8 0	27	
13	Mortar Bond over roof brick in chunam ..	,,	0 8 0	57	
14	Plastering with mortar 2 coats	Sqr.	3 8 0	29	
15	Cement pointing	,,	4 0 0	2.71	
16	Painting two coats of chocolate	,,	4 0 0	10.59	
17	Flooring with ordinary concrete and cement plastering cut in sqrs.	,,	15 0 0	4.33	
18	Coping 9″ thick	,,	0 8 0	60	
19	Drains	L. S.	..	25	
20	Unforeseen charges..	L. S.	..	46	
21	White washing 2 coats	Sqr.	0 4 0	29	

R. TIPPAIYA,
Executive Engineer.

MEDICAL DEPARTMENT

MENTAL HOSPITAL, BANGALORE CITY.

Abstract Notification dated 30th July 1936.

Sealed tenders in triplicate for the supply of Bedding and Clothing required for the use of the Mental Hospital, Bangalore, for the year 1936-37, will be received by the undersigned at 11 A.M. on Monday the 7th September 1936. For full particulars, please see pages 1126-1127 of Part VI of the *Mysore Gazette*, dated 23rd July 1936.

M. V. GOVINDASWAMY,
Superintendent.

OFFICE OF THE SUPERINTENDENT, MEDICAL STORES, MYSORE GOVERNMENT, BANGALORE CITY.

Notification dated 11th August 1936.

Notice is hereby given that the undermentioned unserviceable articles will be sold by public auction at 1 P.M., on Thursday the 10th September 1936, by the undersigned in the premises of the Medical Stores.

The full amount of the bid must be paid immediately and the things removed then and there :—

(1)	Empty Iron Drums	80
(2)	,, Tins keroseine oil	25
(3)	,, ,, small	1 lot.
(4)	,, Bottles	1 lot.
(5)	Deal-wood cases and crates	1 lot.
(6)	Iron bands and wire pieces	1 lot.

M. HIRANYAIYA,
Superintendent.

MISCELLANEOUS DEPARTMENTS

INDIAN POSTS AND TELEGRAPHS DEPARTMENT.

OFFICE OF THE SUPERINTENDENT OF POST OFFICES BANGALORE DIVISION,

Notice No. G—39-3, dated Bangalore the 28th July 1936.

1. Sealed tenders are invited for the conveyance of mails by motor vehicles daily between Tumkur and Sira, throughout the year on a fixed monthly subsidy for a period of two years and eight months from 1st October 1936. The daily average mileage at present involved is 64 miles.